

Corle Building Systems

Factory Mutual Approval - Seam Lok



FM Rating	RoofNav No.	Width	Gauge	Purlin Spacing	Fasteners Per Clip	Wind Clamp
Class 1-60	117-0-0	24"	24	4'-0"	2	N/A
Class 1-90	119-0-0	18"	24	5'-0"	2	N/A
Class 1-105	118-0-0	24"	22	4'-0"	2	N/A
Class 1-120	341240-0-0	24"	22	5'-0"	3	1
Class 1-135	341239-0-0	18"	24	5'-0"	3	1
Class 1-150	341241-0-0	24"	22	*5'-0"	3	2

****Requires 14-Gauge Minimum Purlin***

1. Test procedures are in accordance with Factory Mutual Research Corporation (FMRC) Standard 4471.
2. A detailed test report is available for each product above. The panels must be installed in a specific manner to achieve the published result. Contact Corle for more information.

“Building Trust In Steel”